

Timber Lane Culvert Replacement Project

Project Information: The project replaces the large, corrugated metal arch culvert pipe that is located between Ken Dr. and Oak Crest Dr. with a new horizontal elliptical reinforced concrete pipe. To complete this work, sanitary sewer main, storm sewer main, and watermain work will be completed as some portions are in conflict with the culvert installation. There may be a short timeframe when water service is shut off, but notifications will be sent out prior to any shut offs happening. Construction is anticipated to begin on July 15th with a tentative completion of August 9th, weather dependent.

Anticipated Timeline: Construction, July 15, 2024 – Aug 30, 2024

Road Closures, Vehicles & Traffic: While under construction, Timber Ln will be closed between Ken Dr. and Oak Crest Dr. Residents that live on this portion of Timber will have access to their home but will only have access from the side of the culvert they live on. The designed detour route is to have traffic bypass the road closure using Carole Ln to Pioneer Dr to Circle Dr, and vice versa.

Resident Access: Local resident access to and from your home will be maintained as much as possible. Please let the Project Inspector or the Contractor know of any special provisions that may be needed to help you access your property.

Communication: It is the intent of the Village to minimize the amount of disruption and inconvenience to the community during any construction process. If during normal work hours you feel something went unnoticed, or needs attention, please contact **Matt Smith**. As project inspector, he is most familiar with the daily operations of construction and can resolve many issues quickly.

If something happens after normal work hours that you feel requires immediate attention, please call 920-492-2995, and arrangements will be made to resolve the issue. As always, in an emergency, please call 911. Additional information is available on the Village website.

Project Updates: Construction updates will be posted on the Village website bi-weekly, and when major changes will be occurring. If at any time you would like additional information, please contact any of the contacts listed on this page

General Notes:

1. The Village is coordinating with school buses, mail carrier, and garbage/recycling pickup to ensure deliveries and pickups will not be affected by construction.
2. Please remove any irrigation, electric pet fences, landscaping, and other items within the **Right-of-Way**. This is your responsibility and not the Villages.

Two Week Anticipated Outlook:

Week of July 15, 24: Traffic control is scheduled to be installed Monday morning. Erosion control and clearing and grubbing are to follow. Once the bushes and trees are cleared the sanitary sewer and water main relocation work will take place. Once the sewer and water work are completed the culvert replacement will begin.

Week of July 22, 24: The culvert replacement is scheduled to be finished this week and the installation of the new storm sewer features will be installed. After all the pipe networks are installed the area around the new culvert will be leveled off and graded to desired elevation.

Contact information:

Project Inspector

Matt Smith
Village of Ashwaubenon
2155 Holmgren Way
Ashwaubenon, WI 54304
920-615-1600 (Mobile)
msmith@ashwaubenon.gov

Village Engineer

Steve Birr
Village of Ashwaubenon
2155 Holmgren Way
Ashwaubenon, WI 54304
920-492-2308 (Office)
sbirr@ashwaubenon.gov

Director of Public Works

Brian Rickert
Village of Ashwaubenon
2155 Holmgren Way
Ashwaubenon, WI 54304
920-492-2308 (Office)
brickert@ashwabenon.gov

Contractor Project Manager

Chris VandenBush
Advanced Construction Inc.
2141 Woodale Ave
Green Bay, WI 54313
(920) 434-3978 (Office)
(920) 609-1203 (Mobile)
cvandenbush@advconst.net

Important Dates:

Timber Ln is scheduled to be closed starting July 15 at 7:00 am.